BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of the Work : Development of Play Ground at Varadharajangara in Ward No. 11, Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates KRIDL		
				In Figures	Amount	In Words
1	7267.32	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	83.16	604350.33	Rupees Eighty Three and Sixteen Paise Only
2	53.10	Providing and laying in position plain cement concrete of **mix 1:4:8 with OPC cement @ 180 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5070.60	269248.86	Rupees Five Thousand Seventy and Sixty Paise Only
3	212.40	Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6**, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4135.32	878341.97	Rupees Four Thousand One Hundred Thirty Five and Thirty Two Paise Only
4	95.58	Providing and constructing granite / trap / basalt size stone masonry in **basement with cement mortar 1:6**, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4905.36	468854.31	Rupees Four Thousand Nine Hundred Five and Thirty Six Paise Only
5	212.40	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4 etc complete as per specifications and directions of engineer in charge of the work	Sqm	97.20	20645.28	Rupees Ninety Seven and Twenty Paise Only
6	21.24	Providing and laying in position plain cement concrete of **mix 1:2:4 with OPC cement @ 240 kgs with 40mm** and down size graded granite metal coarse aggregares @ 0.878 cum and fine aggregates @ 0.459 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5404.32	114787.76	Rupees Five Thousand Four Hundred Four and Thirty Two Paise Only
7	480.00	Supplying and fixing M.S rectangular poles made out of 2 equal angles of 65x656 mm welded together and fixed in CC (1:2:4) with 2 NOS 16 mm dia, M.S hold fast rods each of length 25 cms, including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer in charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) etc complete as per specifications and directions of engineer in charge of the work	M	991.44	475891.20	Rupees Nine Hundred Ninety One and Forty Four Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

24/X/16

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates		
				KRIDL		
				In Figures	Amount	In Words
8	1416.00	Providing and fixing M.S. Block pipe of 38 mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the two vertical poles (M.S rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the engineer in charge of work etc, complete including two coats of approved quality paint over one coat of shop paint etc complete as per specifications and directions of engineer in charge of the work	M	338.04	478664.64	Rupees Three Hundred Thirty Eight and Four Paise Only
9	708.00	Providing chain link fencing 50 mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall bed welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the engineer – in charge of work including two coats of approved quality paint over one coat of shop paint etc complete as per specifications and directions of engineer in charge of the work	Sqm	697.68	493957.44	Rupees Six Hundred Ninety Seven and Sixty Eight Paise Only
10	6.30	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 gaguge M.S hollow pipe frame work bent to ornimental shape as shown in the drawing and 35 mm x 6 mm and 16 x 16mm squate roads for verticals alternatively spaced at 4 cms c/c in two halves and 40 mm x 6mm M.S Flates for horizontal memeber and at the top cast iron spikes are provided at alternate vertical member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc complete all the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (Shop Paint) etc complete the work includes cost of all materials labour charges, for all items of work, hire chargesfor welding cutting and grainding equipment and electtricity charges with lead and lift loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Sqm	3299.40	20786.22	Rupees Three Thousand Two Hundred Ninety Nine and Forty Paise Only
11	7121.97	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. **From 0.00 to 11.90 Km** etc complete as per specifications and directions of engineer in charge of the work	Cum	106.34	757350.29	Rupees One Hundred Six and Thirty Four Paise Only
		Total			**4582878.29**	

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

24/X/16